

Project Purpose:

The purpose of this project is to improve safety and traffic operations at the intersection of State Route 41 and O'Neals Road/Road 200 in Madera County. This intersection is a primary route for the near by communities of Northfork, Coarsegold and Oakhurst and serves as a main route to Yosemite National Park. This intersection is located adjacent to a Park & Ride facility.

This project will improve safety by installing traffic signals, constructing turn lanes and extending passing and acceleration lanes within the project limits.

Project Description:

This project will consist of signalization and upgrades at the intersection of State Route 41 and O'Neals Road/Road 200 in Madera County. This area forms a T-intersection and will include lighting and the addition of a right-turn and acceleration lanes on the northeast and southeast corners. The passing lanes on State Route 41 in the northbound direction will be extended south of the O'Neals Road/Road 200.

Construction Cost: \$1.7 Million

Begin Construction: April 2007

End of Construction: June 2007

Funding Sources:

State Highway Operation and Protection Program (SHOPP), Madera County

Contractor:

W. Jaxson Baker, Inc.

Update:

60% complete, signalization to be installed mid-June, Park and Ride Facility to remain closed for the duration of the project.

Project Map on Reverse

